Temple Street Watermain – Route 3 Bridge Crossing

Owner:	**Water Department, Department of Public Works** **Duxbury, MA**
Contact:	**Paul Anderson, Water Superintendent** **878 Tremont Street** **Duxbury, MA 02332**
Telephone:	**781-934-1103**
Key Personnel:	**David A. Jacobsen, P.E.** **Patrick G. Brennan, P.E.**

Project Description

The project included approximately a mile of 12-inch ductile iron watermain with a river crossing and state highway bridge crossing. Bridge work included modifications to the bridge structure to provide a shelf for the watermain. The watermain was placed on roller assemblies, insulated and tied down with stainless steel straps.